

**NAME OF THE WORK:** Estimation for Construction of Ground Floor R.C.C Building at Cheepurapalli Village & Grama panchayathi, Cheepurupalli Mandal, Vizianagaram Dist.

Sl.No.	Description of item	Unit	Quantity	Rate (in Rs.)	Amount
					(in Rs.)
1	Slab Area Flooring in CM (1:3) 12mm thick including the cost and conveyance of all materials and labour charges etc.,	Sqm.	167.08		
2	Providing and laying C.C flooring in C.M.(1:3) including the cost and conveyance of all materials and labour charges	sqm.	62.16		
3	Brick Masonry in C.M.(1:6) using Ist class Bricks including cost and conveyance of all materials and labour charges etc., complete for item of work for main walls @ 9" Walls Brick work	Cu.m	12.79		
4	Plastering in C.M.(1:6) with 12 mm thick to the Brick masonry walls for the internal and external faces including the cost and conveyance of all materials and labour charges etc., compound wall Outside & Inside	Sqm.	111.19		
5	Painting To compound wall surface Applying two coats of whitewash and total Building inside and outside	Sq.m	111.19		
		Sq.m	329.18		
6	Provision for Main gate	Lump sump			